

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (county) Located In: Corner Code #
Holly Township
1. Public Land Survey T 5N R 7E L-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

1999
LIBER 20945 PAGE 594
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
01/04/2000 07:37:46 A.M. RECEIPT# 342
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS
REGISTERED ON: 3-3-99
Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, James E. Kovas, in a field survey on February 19, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-K and rows 2-13. Contains numbers 6, 5, 4, 3, 2, 7, 8, 9, 10, 11, 18, 17, 16, 15, 14, 19, 20, 21, 22, 23, 30, 29, 28, 27, 26, 31, 32, 33, 34, 35.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-3
1816 - G.L.O., Alex Holmes, D.S., set post
1992 - Chris Newman #24607 (LCRC Liber 13294, Page 134) found 1/2" rerod

Distances: L-3 to M-3 = 2723.84' (Wade-Trim, 1999)
L-3 to M-3 = 2726.17' (Holly survey Baldwin, 1940)
L-3 to K-3 = 2683.91' (Wade-Trim, 1999)
L-3 to K-3 = 2684.31' (Newman, 1992)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 Found 1/2" iron.


WITNESSES FOUND:

Verified this corner with distance north to found property iron as per tax maps. 38.84' (M) 38.89' (R)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 Found 1/2" iron pipe in South and SE fence line. Removed and replace with concrete monument cap #33138.

WIT: N 60 W 17.21' Set P.K./tag #33138 8" Cherry
N 15 E 21.45' Set P.K./tag #33138 8" Walnut
South 3.52' Set P.K./tag #33138 16" Walnut
N 80 E 32.59' Set P.K./tag #33138 8" Oak
North 38.38' Property corner



Signed by James E. Kovas Date 12/22/99