LIBER 20945 606

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

2011

LIBER 20945 PAGE 606
$7.00 MISC RECORDING
$2.00 REMONUMENTATION
01/04/2000 07:37:46 A.M. RECEIPT# 342
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF

3-3-99 55

Register of Deeds Stamp & File Number

For corners in

Oakland (county)

		Located In:	Corner Code #
		Holly Township	
1. Public Land Survey		T 5N R 7E	M-7
		T___ R___	
		T___ R___	
		T___ R___	
2. Property Controlling	S___	T___ R___	
in Section	S___	T___ R___	
3. Miscellaneous	S___	T___ R___	
Property in Sec.	S___	T___ R___	

SURVEY & RE... ATION
MAR 21 2000
SECTION

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____



I, James E. Kovas, in a field survey on December 17, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines I and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United Slates Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-7
1816 - G.L.O., Alex Holmes, D.S., set post

Distances:
M-7 to M-6 = 2590.44' (Wade-Trim, 1998)
M-7 to M-8 = 2590.44' (Wade-Trim, 1998)
M-7 to L-7 = 2696.54' (Wade-Trim, 1999)
M-7 to A-7 = (Groveland) 539.59' (Wade-Trim/Kieft, 1998)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-7 No corner found. Corner is in a gravel pit at Mt. Holly.

The corners M-7 and M-8 fall within the gravel pit. No evidence was found of the corners. The corners were computed by using 1/3 of the distance between M-6 and M-9. M-7 was placed on a line projected through M-6 and A-7 since A-7 is the best evidence of the original location of the Township line. M-8 as placed on line between the computed M-7 position and M-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-7 Set concrete monument with cap #33138 in fence line.

WIT:	N 12 E	21.88'	Set P.K. nail w/tag #33138 16" Oak SE face
	S 55 E	6.60'	Set P.K. nail w/tag #33138 8" Oak
	S 20 E	20.84'	Set P.K. nail w/tag #33138 14" Oak
	N 89 W	12.44'	Set P.K. nail w/tag #33138 4" twin Oak

STATE OF MICHIGAN
JAMES E. KOVAS
LAND SURVEYOR
No. 33138
REGISTERED LAND SURVEYOR

Signed by James E. Kovas Date 12/22/99

Surveyor's Michigan License No. 33138

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983