

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Oakland

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|--|-------------------------|--------------------|
| 1. PUBLIC LAND SURVEY _____ 30 T. _____ 5 N. _____ 8 E. _____ | _____ S. _____ R. _____ | A-11, A-10 |
| 2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____ | | |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____ | | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-11 SW Corner
Set 4" x 36" Concrete monument
w/cap on townline @ G.L.O. Jog.

A-10 W 1/4 Corner
Set 3" x 8' plastic pipe with 1" iron
Pipe and cap inside and filled with
concrete on townline @ G.L.O. Jog.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 SW Corner
4" x 36" Concrete mon. w/cap
S66°E - 32.69' - 8" Cherry
S08°W - 17.19' - 15" Cherry
N17°E - 34.64' - 20" Cherry
N45°E - 12.05' - 7" Cherry

A-10 W 1/4 Corner
3" x 8' plastic pipe w/1" iron pipe
and cap inside and filled w/concrete
S80°W - 25.64' - 3" Elm
N08°E - 34.15' - 4" Tumarack
S53°E - 34.30' - 8" Tumarack
N85°W - 139' - edge of swamp.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

