

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>14</u> T. <u>5</u> N. <u>8</u> R. <u>8</u> E. <u>W</u>		<u>J-5, J-6</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on April, 1977, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>J-5 Recovered old fence corner placed 1" iron pipe with plastic cap</p>	<p>J-6 Set at the intersection of the N-S and E-W 1/4 lines 1" iron pipe with plastic cap</p>
--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>J-5 1" iron pipe with plastic cap  N.73°E. 12.82' 12" cherry  S.63°W. 18.63' 25" white oak  N.24°E. 33.32' 9" black oak  N.73°W. 10.91' 5" maple</p>	<p>J-6 1" iron pipe with plastic cap  S.40°W. 29.39' triple 3",5",7" black cherry  S.55°W. 27.57' 4" ash  N.25°W. 20.18' twin 4" ash  N.69°E. 28.75' 16" black oak</p>
---	--

All distances are to spikes in the trees.

SIGNED BY Donald L. Bissell DATE June 13, 1977

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Donald L. Bissell DATE June 13, 1977  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655