

MAR 21 2000

LIBER 19758 PG 408

COPY

SECTION

106222

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 19758 PAGE 408

For corners in Oakland (County)

Located In:

Corner Code #

\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
03/30/1999 01:03:21 P.M. RECEIPT# 12968
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 3-10-99 JS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 5N R 8E A-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. A star is marked at row 5, column A.

I, Timothy J. Hart, in a field survey on 2-15, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in lake noted in 1823 G.L.O. survey. Closing corner located 7.00 chains (452 ft) north of Holly Twp. corner M-5.

Survey, L6270, P249, Jones, 1974, corner shown on Twp. line, located 521.40 ft north of the NE corner of Section 13, T5N, R7E, Holly Twp. (M-5) in Horton Lake.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner location falls in Horton Lake. Old fence line remnants were recovered running south on the south side of the lake, running through the NE corner of Section 13, T5N, R7E, Holly Township (M-5). The location of the corner was calculated on the Township line between Holly Township corners M-5 and M-4, located 521.40 ft north of M-5.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with O.C. remonumentation brass cap at reference point location on the Township line 329.29' north of corner A-5.

- N 30°W 25.18' PK/remon tag E. 28" Maple
N 45°E 19.48' PK/remon tag NW 12" Willow
S 70°E 24.35' PK/remon tag N. 16" Oak
West 37.95' PK/remon tag S. 12" Oak

State Plane Coordinates of A-5
N 490980.7187
E 13336966.8345

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by Timothy J. Hart
Surveyor's Michigan License No. 33136

Date 3-5-99