

MAR 21 2000

COPY

LIBER 19758 PG 425

106239 SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Oakland</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>8E</u>	<u>C-2</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

19758 PAGE 425
 MISC RECORDING
 REMONUMENTATION
 03/30/1999 01:03:21 P.M. RECEIPT# 12968
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 6-15-98 JS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Timothy J. Hart, in a field survey on 2-18, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	•	5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:
Post set in 1823 G.L.O. survey; 12" Hickory N 78°W 265 lks.

- | | |
|-------------------------|---|
| LCRC, L6716, P750, | Survey, L15011, P772, |
| Albright, 1974, 1" pipe | Lukasavitz, 1994, 3/4" pipe |
| *N 40°E 37.60' 15" Oak | *S 20°E 91.68' PK/washer W. PP |
| *S 20°E 91.68' P.Pole | North 26.34' Nail/tag 17623, E. 10" Oak |
| *North 25.30' 6" Oak | *N 40°E 37.33' PK W. 24" Oak |
| | *S 80°E 109.99' Nail/tag G.E.1, S 48" Oak |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Recovered a 1" pinch top pipe 8" below the gravel surface in the centerline of Groveland road. A tree/fence row runs north from the corner.

- Witnesses Recovered
- *North 25.31' Nail/tag #17623 E. 12" Oak
 - N 20°E 45.45' Nail/cap W. 12" Ash
 - *N 40°E 37.73' PK nail W. 24" Oak
 - S 80°E 109.70' Nail/cap #9189, S. 50" Oak
 - *S 80°E 110.05' Nail/cap #25858 S. 50" Oak
 - S 80°E 110.09' Nail/tag #17623 S. 50" Oak
 - *S 20°E 91.28' & 91.81' Nail/tags 9189 & 17623 in U pole

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: *Confirms LCRC or survey

- Set 5/8" rerod w/O.C. Remon brass cap, replacing 1" pinch top pipe.
- | | |
|---|-------------------------|
| N 20°E 45.48' PK/remon tag W. 12" Ash | State Plane Coordinates |
| N 40°E 37.39' PK/remon tag W. 24" Oak | N 499090.0557 |
| S 80°E 109.98' PK/remon tag S. 50" Oak | E 13341990.3971 |
| S 20°E 91.72' PK/remon tag E. util pole | |



The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by Timothy J. Hart
Surveyor's Michigan License No. 33136

Date 6-2-98