

COPY

LIBER 19758 PAGE 449

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

106263

Oakland Located in: Corner Code #
(County)

1. Public Land Survey T5N R 8E E-6
SURVEY &
T R RE-REMONUMENTATION
T R
T R
2. Property Controlling S T R MAR 21 2000
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R SECTION

LIBER 19758 PAGE 449
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
03/30/1999 01:03:21 P.M. RECEIPT# 12968
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 8-27-98 JS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Timothy J. Hart, in a field survey on 2-28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column E and row 6.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1823 G.L.O. survey; 6" B Oak S 73°E 48 lks; 12" Hickory N 32°W 22 lks.
A) Survey, L6651, P359, Pangus, 1976, fd 1/2" pipe (3)
B) LCRC, L11604, P642, Newman, 1990, fd 1/2" pipe (4)

(n) indicates number of witnesses confirmed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 1/2" pipe in a north and south tree/fence/rock row. A tree row runs east from the corner. Corner is located off road, 1/2 mile south of Perryville Road, 1/2 mile north of Grange Hall Road, and 3/4 mile west of Barron Road.

Witnesses Recovered

North 8.39' Nail E fence post (A&B)
East 6.14' Nail/tag S 36" Oak (A&B)
South 36.52' Nail/tag E Twin 12" Oak (B)
South 25.00' Iron rd (A&B)

(L) indicates survey or LCRC witness confirmed

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with O.C. remonumentation brass cap, replacing 1/2" pipe.

N 45°W 30.40' PK/remon tag NE 4" Oak State Plane Coordinates
East 6.14' PK/remon tag S 36" Oak N 488731.8509
S 45°E 45.04' PK/remon tag SW DE pole E 13347646.1848
South 36.52' PK/remon tag E Twin 12" Oak

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by Timothy J. Hart
Surveyor's Michigan License No. 33136

Date 8-24-98

