

COPY

LAND CORNER RECORDATION CERTIFICATE 106265  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland  
(County)

Located in:

Corner Code #

LIBER 19758 PAGE 451  
\$7.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
03/30/1999 01:03:21 P.M. RECEIPT# 12968  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

1. Public Land Survey

T 5N R 8E E-8  
T R SURVEY &  
T R RE-REMONUMENTATION  
T R

2. Property Controlling in Section

S T R  
S T R MAR 21 2000

3. Miscellaneous Property in Sec.

S T R  
S T R SECTION

Compliance with ACT 345, P.A. 1990

APPROVED ON: 1-27-99 JS  
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Timothy J. Hart, in a field survey on 11-13, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1823 G.L.O. survey; 8" W. Oak N 36°W 31 lks; 14" B. Oak S 79°E 44 lks.

No subsequent record of restoration.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Searched an area within the west campground of the Holly Recreation Area for monumentation and occupational evidence. Located the intersection point of heavy rock/tree rows running north, south, east and west from the corner. A concrete monument was set with Oakland County remonumentation brass cap at the intersection point. The monumented point falls 12.82 feet east of a straight line between Corners E-7 and E-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with O.C. remonumentation brass cap 32 feet east of campground road.

North 9.62' PK/remon tag W. 12" Elm  
East 7.72' PK/remon tag S. 38" Oak  
South 5.65' PK/remon tag E. 8" Maple  
West 69.40' PK/remon tag S. 32" Oak

State Plane Coordinates  
N 483473.3397  
E 13347828.1237

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by Timothy J. Hart  
Surveyor's Michigan License No. 33136

Date 1-23-99