

COPY

LIBER 19758PG485

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

106299

For corners in

Oakland
(County)

Located In:

Corner Code #

1. Public Land Survey

T 5N R 8E I-2

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

SURVEY &
REMONUMENTATION

MAR 21 2000

LIBER 19758 PAGE 485
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
03/30/1999 01:03:22 P.M. RECEIPT# 12968
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 6-15-98 JS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____ SECTION _____
5. Private Claims _____

I, Timothy J. Hart, in a field survey on 3-17, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1823 G.L.O. survey; 12" W. Oak N 35 1/2° E 24 lks; 10" W. Oak S 78 1/2° W 32 lks

- A) LCRC, L 6022, P 361, Stonerock, fd 1" pipe, 1973 (3)
- B) LCRC, L 6468, P 116, Pangus, fd 1" pipe, 1975 (3)
- C) LCRC, L 14419, P 394, Kennedy, fd 1/2" pipe, 1993 (3)
- D) LCRC, L 17188, P 326, Ward, fd 1/2" pipe, 1997 (4)

(n) indicates the number of witnesses confirmed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 1/2" iron pipe 8" below grade in the centerline of Jossman Road approximately 5 ft south of the centerline of Auten Road. A tree/rock row runs west from the corner.

Witnesses Recovered

- N 40°W 48.49' Tag #22445 NE 40" Maple (A,B,&D)
- N 40°W 48.07' Tag #17623 SW 40" Maple (C)
- N 45°E 56.38' Tag #17623 SE 40" Maple (A,B,C,&D)
- N 45°E 55.93' N/C SE 40" Maple
- N 65°E 64.11' N/C S Twin Walnut
- S 25°W 67.91' Tag #22445 E 10" Walnut (D)
- S 70°W 34.40' PK N dead 40" Maple (A,B,C&D)

(L) indicates LCRC confirmed

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rerod with O.C. Remon. brass cap, replacing 1/2" iron pipe.

- N 40°W 48.61' PK/remon tag E 40" Maple
- N 45°E 56.40' PK/remon tag E 40" Maple
- N 65°E 64.34' PK/remon tag S twin 12" & 6" Walnuts
- S 25°W 67.85' PK/remon tag E 10" Walnut

State Plane Coordinates

N 499703.3634
E 13357660.2980

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by Timothy J. Hart
Surveyor's Michigan License No. 33136

Date 5-20-98

