

COPY

106322

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1990

For corners in

Oakland
(County)

Located In:

Corner Code #

1. Public Land Survey

T 5N R 8E K-5

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

SURVEY & RECORDATION

MAR 21 2000

19758 PAGE 508
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
03/30/1999 01:03:22 P.M. RECEIPT# 12968
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 8-27-98 JS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ SECTION _____
5. Private Claims _____

I, Timothy J. Hart, in a field survey on 6-5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5		4		3		2			
3											
4	7	8		9		10		11		12	
5											
6	18	17		16		15		14		13	
7											
8	19	20		21		22		23		24	
9											
10	30	29		28		27		26		25	
11											
12	31	32		33		34		35		36	
13											

A. Description of original monument and accessories and/or subsequent restoration:

- Post set in 1823 G.L.O. survey; 18" Aspen N 56°E 61 lks; 12" W. Oak S 31° 163 lks.
- LCRC, L6941, P503, Bissell, 1977, Fd 1/2" iron, replace w/3/4" pipe & cap
 - S 87°E 25.53' 8" Cherry
 - *S 30°W 41.66' 24" Cherry
 - *N 20°W 88.31' 12" Cherry
 - *N 42°W 26.72' 6" Cherry
- LCRC, L9841, P301, Kennedy, 1987, Fd 3/4" iron pipe
 - *N 10°E 99.70' PK W. 16" Oak
 - *S 15°W 42.06' PK E. 16" Cherry
 - *N 05°W 88.64' PK W. 15" Cherry

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 3/4" pipe 10 ft west of the centerline of Brandt Road. Corner is located in the Holly Recreational Area.

Witnesses Recovered

- *N 40°W 26.80' PK W. 14" Cherry
- *N 10°W 88.40' PK E. 16" Cherry
- *N 10°W 88.71' Nail/tag 17623 W. 16" Cherry
- *N 25°E 99.69' Nail/tag 17623 E. 16" Oak
- *S 25°W 41.40' PK E. 22" Cherry
- *S 25°W 42.10' Nail/tag 17623 E. 22" Cherry

*Confirms LCRCs

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rerod, 8' long, w/O.C. remonumentation brass cap, replacing 3/4" iron pipe.

- N 40°W 26.70' PK/remon tag SW 14" Cherry
- N 10°W 88.21' PK/remon tag E. 16" Cherry
- S 45°E 94.95' PK/remon tag S. Triple 16" Maple
- S 25°W 41.31' PK/remon tag E. 22" Cherry

State Plane Coordinates
N 492001.7321
E 13363243.1734

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by Timothy J. Hart
Surveyor's Michigan License No. 33136

Date 8-25-98

