

COPY

LIBER 19758 PAGE 510

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

106324

For corners in

Oakland (County) Located in: Corner Code #
1. Public Land Survey T5N R8E K-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

LIBER 19758 PAGE 510
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
03/30/1999 01:03:22 P.M. RECEIPT# 12968
PAID RECORDED - OAKLAND COUNTY
B. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 11-05-98 JS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

MAR 21 2000

4. Lot No. Recorded Plat SECTION
5. Private Claims

I, Timothy J. Hart, in a field survey on 5-23, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. A dot is marked at row 7, column K.

- A. Description of original monument and accessories and/or subsequent restoration: Post set in 1823 G.L.O. survey; 15" Jack Pine N 47°E 23 lks; 9" W. Oak S 05°W 15 lks.
A) LCRC, L6305, P694, O.C.R., Brown, 1974, set 1/2" rerod & cap (0)
B) "Woodland Pines", L208, P17-21, Carlson, 1989 (0)
C) Survey, Delta, Phillips, 1990 (2)
D) "Quail Run Estates", L15288, P618 (1)

(n) indicates number of distance verifications

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Recovered a 1/2" rerod with Delta cap (#19002) on an E-W farm fence. A fairly distinct tree row runs N & S from the corner. No other corner evidence was recovered.
North K-7 to K-6: 2632.29' (mea.); 2632.58' (C)
East K-7 to L-7: 2642.24' (mea); 2642.10' (D); 2651.37' (B)
South K-7 to K-8: 2613.40' (mea)
West K-7 to J-7: 2629.75' (mea); 2629.82' (C); 2622.98' (A)

(1) LCRC, survey, subdivision or condominium referenced

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Set concrete monument w/O.C. remonumentation brass cap, replacing 1/2" rerod & cap.
N 45°W 4.70' PK/remon tag S. 12" Poplar State Plane Coordinates
N 20°E 12.75' PK/remon tag W. 10" Poplar N 486747.1327
East 9.55' PK/remon tag S. 10" Poplar E 13363501.5915
S 40°W 21.78' PK/remon tag SE 14" Poplar

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by Timothy J. Hart
Surveyor's Michigan License No. 33136

Date 10-26-98



Handwritten initials 'JP' and 'R'.