

COPY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

106331

For corners in

Oakland
(County)

Located in:

Corner Code #

1. Public Land Survey

T 5N R 8E

L-1

T R

T R

T R

S T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

SURVEY &
REMONUMENTATION

MAR 21 2000

LIBER 19758 PAGE 517
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
03/30/1999 01:03:22 P.M. RECEIPT# 12968
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 6-15-98
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ SECTION

5. Private Claims _____

I, Timothy J. Hart, in a field survey on 3-28, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

Corner was not set in the 1815 or 1823 G.L.O. surveys.

LCRC, L7177, P595, Scharl, 1978, 1/2" iron

Survey, L7538, P900, Henderson, 1979

*N 45°W 23.50' PK SW 9" Cherry

Survey, L9134, P429, Henderson, 1985

*N 50°E 39.95' PK S 23" Oak

*N 50°E 39.62' 36" Oak

S 15°E 25.68' PK E twin 16" Oaks

*South 21.53' 12" Triple Oak

*N 30°W 23.50' 7" W. Cherry

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 1/2" rered in the centerline of County Line Road (Ray Road).

Also recovered a 5/8" rered 61.83 ft east in the centerline at the S 1/4

corner of Section 36, T6N, R8E, Atlas Township (L-13).

Witnesses Recovered

*N 45°W 23.43' PK/tag 17623 W 14" Cherry

*N 40°E 39.77' PK/tag 17623 S 48" Oak

*N 40°E 39.52' Nail S 48" Oak

*South 21.71' Nail E Triple 18" Oaks

*Confirms LCRC's

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rered w/O.C. Remon brass cap 0.72 ft south of recovered 1/2" rered on township line.

N 45°W 23.96' PK/remon tag W. 14" Cherry

N 40°E 39.98' PK/remon tag S. 48" Oak

S 45°E 82.43' PK/remon tag W. utility pole

South 20.98' PK/remon tag E. triple 18" Oaks

State Plane Coordinates

N 502718.7473

E 13365438.4570

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by Timothy J. Hart

Date 6-11-98

Surveyor's Michigan License No. 33136

