

COPY

LIBER 19758PG528

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

106342

For corners in

Oakland  
(County)

Located In:

Corner Code #

1. Public Land Survey

T5N R 8E M-5

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

SURVEY &  
REMONUMENTATION

MAR 21 2000

SECTION

LIBER 19758 PAGE 528  
\$7.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
03/30/1999 01:03:22 P.M. RECEIPT# 12968  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 6-15-98 JS  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Timothy J. Hart, in a field survey on 3-30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1815 G.L.O. survey; 6" Tamarack S 14°E 15 lks; 6" Tamarack N 03°W 35 lks

No other record land corners or surveys.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" rerod in a swamp area on an old fence line running east and west from the corner.

The 1/2" rerod is located 0.23 ft east of a straight line between Corners M-4 and M-6. Distance measured west to Corner L-5 is confirmed by the record distance along the south line of the E 1/2 of Section 12; 2670.40' (M), 2670.38' (rec. Sec. 12).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 5/8" rerod, 6' long, with O.C. Remon. brass cap, replacing 1/2" rerod.

N 40°E	127.25'	PK/remon tag N 10" Poplar	State Plane Coordinates
East	12.34'	PK/remon tag top of cedar post	N 492264.5966
East	148.60'	PK/remon tag S 8" Cherry	E 13368579.4959
S 45°E	15.43'	PK/remon tag top of cedar post	
S 85°W	34.46'	PK/remon tag N 3" Ash	

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by Timothy J. Hart  
Surveyor's Michigan License No. 33136

Date 5-29-98