

COPY

LIBER 19758 PG 530

LAND CORNER RECORDATION CERTIFICATE 106344
Filing Requirement of Act 74, Mich. P.A. 1970 19758 PAGE 530

For corners in

Oakland
(County)

Located in:

Corner Code #

1. Public Land Survey

T5N R 8E M-7
T R
T R
T R

2. Property Controlling in Section

S T R
S T R

SURVEY & REMONUMENTATION

3. Miscellaneous Property in Sec.

S T R
S T R

MAR 21 2000

\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
03/30/1999 01:03:22 P.M. RECEIPT# 12968
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 11-05-98 JS
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____ SECTION _____
5. Private Claims _____

I, Timothy J. Hart, in a field survey on 10-28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

Post set in 1823 G.L.O. survey; 12" W. Oak S 15°E 60 lks; 15" W. Oak N 41°W 98 lks.

LCRC, L17068, P654, Stonerock, 1997, fd 1/2" rerod

- *S 57°E 46.45' Nail/ALS Tag N. 16" Oak
- *Due South 4.25' Nail/HKK Tag E. 8" Oak
- *S 26°W 33.60' Nail/HKK Tag W. 16" Oak
- *N 40°W 49.25' Nail/HKK Tag SW 20" Oak

IP
R

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a concrete monument located by electrical meter post in trailer park. Confirmed corner with local property surveys.

Witnesses Recovered

- *S 57°E 46.42' Nail/ALS Tag N. 16" Oak
- *Due South 4.25' Nail/HKK Tag E. 8" Oak
- *S 30°W 33.60' Nail/HKK Tag W. 16" Oak
- *N 40°W 49.28' Nail/HKK Tag SW 20" Oak

*Confirms LCRC



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set O.C. remonumentation brass cap on existing concrete monument between trailers 10 & 12.

- N 40°W 49.28' PK/remon tag S. 18" Oak
- N 10°E 3.90' PK/remon tag W. elec meter pole
- S 05°E 4.34' PK/remon tag E. 8" Oak
- S 30°W 33.61' PK/remon tag W. 16" Oak

State Plane Coordinates
N 487008.7914
E 13368805.4616

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner. This corner was also accepted by the Oakland County Peer Group as established under Act 345 of P.A. 1990.

Signed by Timothy J. Hart
Surveyor's Michigan License No. 33136

Date 11-4-98