

SURVEY & REMONUMENTATION

LIBER **14960** PC **087**

94 **242417**

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970: 7.00

MISCELLANEOUS RECORDING \$ 2.00 REMONUMENTATION

For corners in

Oakland

(County)

Located in: Brandon Township

Corner Code #

- | | | | | | | | |
|------------------------------------|---|----------|---|---|----------|---|------------|
| 1. Public Land Survey | T | <u>5</u> | N | R | <u>9</u> | E | <u>K-2</u> |
| | T | | R | | | | |
| | T | | R | | | | |
| | T | | R | | | | |
| 2. Property Controlling in Section | S | | T | R | | | |
| | S | | T | R | | | |
| 3. Miscellaneous Property in Sec. | S | | T | R | | | |
| | S | | T | R | | | |

8 SEP 94 3:15 P.M. RECEIPT# 134B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-29-93
OAKLAND COUNTY REMONUMENTATION
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	

I, Huston K. Kennedy, in a field survey on October 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817 GLO - Wampler, D.S.; Set post; 15" Red Oak S83°W 24 lks; 12" Red Oak S75°E 30 lks
1977 Kennedy, P.S. #17623; LCRC L.7067, Pg.315 - Fnd 1/2" iron rod
1979 Smith, P.S. #21582; Survey L.7593, Pg.337-338 - Fnd 1/2" iron rod
1993 Kennedy, P.S. #17623; Survey L.13452, Pg.009-011 - Fnd 1" iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Huston Kennedy, P.S. #17623 - Fnd a 1" iron pipe 6" ± under the road surface and 3' ± East of the center of Hurd Road, which is gravel. The witnesses from the 1993 survey are still existing. They were used to recover and verify the found 1" iron pipe.

I accepted the 1" iron pipe as the best evidence of the original corner position.

H.K. Kennedy

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 I replaced the found 1" iron pipe with a 5/8" x 24" iron rod with a 2" diameter brass cap stamped Oakland County Remonumentation P.S. #17623.

S21°W-58.83 ft-Set PK & Remon. Tag above existing witness SE face 15" Ash
Due West-30.94 ft-Set PK & Remon. Tag above existing witness North face Power Pole
N15°E-78.25 ft-Set PK & Remon. Tag above existing witness West face 32" Oak
N32°W-36.38 ft-Set PK & Remon. Tag West face 7" Ash

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original position.

Signed by *H.K. Kennedy*
Surveyor's Michigan License No. 17623

Date April 4, 1994

