

SURVEY & REMONUMENTATION

MAY - 1 1995

LIBER 14960 PG 083

94 242413

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

OK - T. SMITH

For corners in

Oakland

(County)

Located In: Brandon Township

Corner Code ##

1. Public Land Survey	T <u>5</u> N R <u>9</u> E	<u>K-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
8 SEP 94 3:15 P.M. RECEIPT# 134B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance with ACT 345, P.A. 1990

APPROVED ON: [Signature]
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	16	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Huston K. Kennedy, in a field survey on October 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817 GLO - Wampler, D.S.; Set post; 15" White Oak N72°E 44 lks; 24" Black Oak N88°W 80 lks
- 1974 Pawlaczyk, P.S. #17632; LCRC L.6247, Pg.721-722 - Set P.K. Nail
- 1974 Buckerfield, P.S. #10868; LCRC L.6260, Pg.666-667 - Fnd P.K. Nail
- 1976 Albright, P.S. #10057; LCRC L.6813, Pg.491-492 - Fnd P.K. Nail
- 1977 Kennedy, P.S. #17623; LCRC L.7067, Pg.315 - Fnd P.K. Nail
- 1993 Kennedy, P.S. #17623; Survey L.13947, Pg.344-346 - Fnd 1/2" iron rod in monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" iron rod in monument box at th intersection of the centerline of Oakwood Road, which is bituminous, and the center of Hur Road, which is gravel.
The witnesses from the 1993 Certificate of Survey are still existing. They were used t recover and verify the found 1/2" iron rod in the monument box.

I accepted the found 1/2" iron rod in the monument box as the best evidence of the origina corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3 I replaced the found 1/2" iron rod in a monument box with a 5/8" x 24" iron rod with a 2 diameter brass cap stamped Oakland County Remonumentation P.S. #17623.

- S62°E-108.95 ft-Set PK/Remon. Tag North face Power Pole
- N73°W-93.88 ft-Set PK/Remon. Tag above existing witness South face 14" Elm
- S38°W-64.45 ft-Set PK/Remon. Tag NW face Power Pole
- S23°W-84.20 ft-PK/Remon. Tag East face 16" Elm

The selected location is accepted by me and is generally accepted by Professionals as the best available evidence of the position of the original position.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date April 4, 1994

