

**SURVEY &
REMONUMENTATION**

MAY - 1 1995

LIBER 14960 PG 086

94 242416

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

Oakland

(County)

Located In: Brandon Township Corner Code #

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 5 N R 9 E | L-1 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
8 SEP 94 3:15 P.M. RECEIPT# 134B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-29-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on October 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817 GLO - Wampler, D.S.; Post set; No witnesses recorded
1974 Pawlaczyk, P.S. #17632; LCRC L.6247, Pg.721-722 - Fnd iron
1979 Smith, P.S. #21582; Survey L.7593, Pg.337-338 - Same wits as 1974 LCRC
1991 Kennedy, P.S. #17623; LCRC L.11996, Pg.025 - Fnd 5/8" iron rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Huston Kennedy, P.S. #17623 - Fnd 5/8" iron rod 3" ± under the road surface located 3' ± South of the center of Davison Lake Road, which is gravel. There is a tree line extending to the South. The witness points from the 1991 LCRC are still existing. They were used to recover and verify the found 5/8" iron rod.

I accepted the found 5/8" iron rod as the best evidence of the original corner position.

File

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 I replaced the found 5/8" iron rod with a 5/8" x 24" iron rod with a 2" diameter brass cap stamped Oakland County Remonumentation P.S. #17623.

S36°W-25.05 ft-Set PK & Remon. Tag above existing witness SE face 12" Cherry
Due South-31.96 ft-Set PK & Remon. Tag East face 14" Elm
N65°E-45.35 ft-Set PK & Remon. Tag SE face 10" Elm
N60°W-29.05 ft-Set PK & Remon. Tag above existing witness SW face 9" Bass

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date April 4, 1995

