

SURVEY & REMONUMENTATION

LIBER 15232 PG 612

FEB 1950 19256

MAY - 1 1995

OK - T. SMITH

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Oakland
(County)

Located In: Brandon Twp. Corner Code #

1. Public Land Survey	T	<u>5N</u>	R	<u>9E</u>	<u>M-3</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
1 FEB 95 8:52 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-27-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on December 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Carpenter, D.S.; No post set - No bearing trees
1.) Bailey, P.S. #33968; Unrecorded Survey - Fnd nothing.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Set a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 based upon GLO proration. The corner was set on a straight line between the East 1/4 corner of Section 1 and East 1/4 corner of Section 12, T5N, R9E. The GLO prorated distance between the standard corner for Brandon Township T4N, R9E, and the closing corner for Oxford Township T5N, R10E, was used to set the corner in the center of Baldwin Road, which has a gravel road extending to the North & South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 I set a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.
N76°W 40.28' Set PK & Remon. Washer North face 22" Maple
N30°W 59.51' Set PK & Remon. Washer SW face Power Pole
N22°E 112.83' Set PK & Remon. Washer West face Power Pole
N29°E 76.19' Set PK & Remon. Washer NW face 9" Box Elder

The selected location is a careful and faithful re-establishment of the position of the original corner



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date January 10, 1995

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

[Handwritten initials]