

MAY - 1 1995

LIBER 15175 PG 145

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Compliance with ACT 345, P.A. 1990

For corners in

Table with columns: Location (Oakland), Located In (Brandon Twp.), Corner Code (#), and numbered items (1-5) describing survey types and their coordinates.

APPROVED ON: 12-14-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
OK - T. SMITH

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
29 DEC 94 9:47 A.M. RECEIPT# 46B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13, containing numbers 1-36.

I, Huston K. Kennedy in a field survey on December 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Carpenter, D.S.; Set Post 10" ? S31°E 18 Links; 5" ? N33°W 6 Links
1.) 1980-Kennedy, P.S. #17623; LCRC L.7791, Pg.744 - Fnd Railroad Spike
2.) 1984-Kennedy, P.S. #17623; LCRC L.8789, Pg.453 - Fnd P.K. Nail
3.) 1972-Jones, P.S. #16045; Survey L.5975, Pg.637 - Fnd Iron Rod
4.) 1975-Kennedy, P.S. #17623; Survey L.6506, Pg.630 - Set Railroad Spike from existing witnesses to corner
5.) 1987-Carlson, P.S. #9189; Unrecorded Survey - Fnd ?
6.) 1991-Kennedy, P.S. #17623; Unrecorded Survey - Fnd ?

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod 0.9' East of the centerline of Baldwin Road, which has a bituminous surface. The West 1/4 corner of Section 18, T5N, R10E, is located 60.84' to the North. There is a line of occupation to the West.

Witnesses from LCRC #2 were used to recover and verify the location of the found 1/2" Iron Rod.

I accept the found 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

Table of field measurements between corners: M-6 to M-7, M-6 to M-5, M-6 to L-6, and M-6 to M-7 with bearings and distances.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-6 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, #17623 in a new monument Box.
N12°W 89.64' NE corner of Concrete Bridge Inbument
N13°E 89.80' NW corner of Concrete Bridge Inbument
N44°E 84.02' Set PK & Remon. Washer North face 12" Poplar
N56°E 28.08' Set PK & Remon. Washer Top of Guard Rail Post
N55°W 24.50' Set PK & Remon. Washer Top of Guard Rail Post

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date December 15, 1994