

MAY - 1 1995

LIBER 15175pc146

Compliance with ACT 345, P.A. 1990

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED ON: 12-14-94 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

For corners in

Table with columns: Oakland (County), Located In: Brandon Twp., Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

\$ 7.00 MISCELLANEOUS RECORDING \$ 2.00 REMONUMENTATION 29 DEC 94 9:47 A.M. RECEIPT# 46B PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

Grid table with columns A-L and rows 2-13, containing numbers 1-36.

I, Huston K. Kennedy, in a field survey on October 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Carpenter, D.S.; Set Post 5" Black Oak N18°W 88 Links; 6" Black Oak S14°W 32 Links 1.) 1973-Jones, P.S. #16045; LCRC L.6124, Pg.216 - Fnd Iron 2.) 1972-Jones, P.S. #16045; Survey L.5975, Pg.637 - Fnd Iron Rod 3.) 1973-Kennedy, P.S. #17623; Survey L.6044, Pg.779 - Fnd Iron Rod 4.) 1987-Carlson, P.S. #9189; Unrecorded Survey - Fnd Iron Rod 5.) 1990-Heil, P.S. #18993; Unrecorded Survey - Fnd 1/2" Iron Rod 6.) 1991-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod in a Monument Box 7.) 1994-Kennedy, P.S. #17623; Unrecorded Remonumentation LCRC - Fnd 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a existing Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a Monument Box located in the centerline of Baldwin Road, which has a bituminous surface 6' South to the centerline of Granger Road to the East, which has a gravel surface and 10' South to the centerline of Granger Road to the West, which has a gravel surface. M-7 T5N, R9E, is being accepted and used as common corner with A-7 T5N, R10E. The GLO Note indicate that M-7 is 53 links (34.98 Ft.) North of A-7.

Witnesses from LCRC #1 and Surveys #2 & 3 were used to recover and verify the location of the found 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a Monument Box. I accept the found 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a Monument Box as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

M-7 to M-6 2643.56 Ft. (Jones 1972) M-7 to M-6 2644.00 Ft. (H. Kennedy 1972) M-7 to M-6 2644.00 Ft. (H. Kennedy 1991) M-7 to L-7 2658.85 Ft. (H. Kennedy 1972)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 I found a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a existing Monument Box. S39°W 65.71' Fnd PK & Remon. Washer NW face 31" Willow S22°E 152.49' Fnd PK & Remon. Washer SW face Power Pole N30°E 65.82' Fnd PK & Remon. Washer SE face Power Pole N69°W 65.68' Fnd PK & Remon. Washer South face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date December 15, 1994

