

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Oakland (County)	Located In:	Corner Code //
1. Public Land Survey	T 5N R 10E	E11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 29 T 5N R 10E	9
	S 29 T 5N R 10E	16
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

16 January 22, 1992  
 9 January 22, 1992

I, Gary C. Bilow, in a field survey on E11 January 21, 1992, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E11: Post established by U.S. Government Deputy Surveyor J. Wampler in 1818; accessory - White Oak 12, S22E 75 links. H. Kennedy, LLS #17623, recorded corner under Act 74, PA 1970 in Liber 10980, Page 235.  
 9: Corner not established by U.S. Government Land Office Survey. Found no record of this corner ever being established.  
 16: Corner not established by U.S. Government Land Office Survey. Found a railroad spike 2.46' North and 1.41' West of the split between corners D11 and E11. The railroad spike fits a tie to a 1/2" pipe referenced to Fernlock Village Sub. Plat as documented in the field notes of Department of Natural Resources Surveyor G.A. Shadko in December 1960. Shadko's field notes do not show a tie to either D11 or E11 and no other evidence was recovered to substantiate this railroad spike.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E11: Found PK nail in Drahner Road and recovered two (2) of Kennedy's witnesses. Accepted corner as the best evidence of the original GLO corner.  
 9: Established corner midway on line between corner D-10 and computed corner E-10. E10 was established by projecting a line from E11 through recovered plat monuments at the record distance as stated on the Fernlock Village Subdivision Plat.  
 16: Established corner midway on line between corners D-11 and E-11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E11: Replaced PK nail with 1/2" x 24" capped rebar in a Monument Box. S6W 35.38', PK nail & Tag in Twin 14" Oak S54W 88.91', N&T in Power Pole S72W 148.38', N&T in Power Pole N28W 29.5', Face of School Crossing Sign North 6', Centerline of Drahner Road	9: Set 1/2" x 36" rebar encased in a 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet in a 4" x 5" PVC pipe filled with concrete S56W 153', End Fence Post S55W 23.69', N&T in 6" Elm S31W 33.03', N&T in 8" Elm S9E 91.82', N&T in 8" Tamarack North 25', Edge of Lake	16: Set 1/2" x 24" capped rebar in Monument Box S10W 49.80', N&T in Power Pole S77W 68.66', N&T in 31" Oak S30E 64.64', N&T in Twin 14" Oak N40E 39.09', N&T in 6-10" Triple Cottonwood N25W 2.74', Railroad Spike
---	---	---

Signed by Gary C. Bilow Date 2/13/92  
 Surveyor's Michigan License No. 26453

