

LIBER 15212 PG 874

OK - T. SMITH

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland
(County)

Located In: Oxford Twp.

Corner Code #

- 1. Public Land Survey T 5N R 10E A-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
20 JAN 95 7:34 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-14-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on August 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. Contains numbers 1-36.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Carpenter, D.S.; Set Post 15" Black Oak S74°E 37 Links; 15" White Oak N52°W 77 Links
1.) 1974-Pawlaczyk, P.S. #17632; LCRC L.2, Pg.663 - Fnd 1/2" Iron Rod (Hadley Twp.)
2.) 1978-Kennedy, P.S. #17623; LCRC L.3, Pg.386 - Fnd 1/2" Iron Rod (Hadley Twp.)
3.) 1974-Pawlaczyk, P.S. #17632; Survey L.2, Pg.886 - Fnd Iron, used same wit as 1974 LCRC (Hadley Twp.)
4.) 1975-Kennedy, P.S. #17623; LCRC L.6575, Pg.155 - Fnd 1/2" Iron Rod (Brandon Twp.)
5.) 1984-Kennedy, P.S. #17623; LCRC L.8789, Pg.452 - Fnd 1/2" Iron Rod (Oxford Twp.)
6.) 1984-Kennedy, P.S. #17623; LCRC L.8789, Pg.453 - Fnd 1/2" Iron Rod, used same wit as 1984 LCRC (Oxford Twp.)
7.) 1974-Kennedy, P.S. #17623; Survey L.6390, Pg.482 - Fnd 1/2" Iron Rod, used same wit as 1984 LCRC (Oxford Twp.)
8.) 1975-Kennedy, P.S. #17623; Survey L.6575, Pg.110 - Fnd 1/2" Iron Rod, used same wit as 1984 LCRC (Oxford Twp.)
9.) 1984-Kennedy, P.S. #17623; Survey L.8646, Pg.459 - Fnd 1/2" Iron Rod, used same wit as 1984 LCRC (Oxford Twp.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod w/2" diameter brass cap stamped "Lapeer County Remonumentation #17623, PS (M-13) for Lapeer County that is 6"± under the road surface and located in the center of the intersection of Baldwi Road and Davison Lake Road. Both have gravel surfaces.

Witnesses from LCRC #1, 2, 4 & 5 were used to recover and verify the location of the found 1/2" Iron Rod w/2" diameter brass ca stamped "Lapeer County Remonumentation" #17623, PS. (M-13)

I accepted the found 1/2" Iron Rod w/2" diameter brass cap stamped "Lapeer County Remonumentation" #17623, PS. (M-13) as the bes evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-1 I found a 1/2" Iron Rod w/2" diameter brass cap stamped "Lapeer County Remonumentation" #17623, PS. M-13
N70°E 30.78' Fnd Nail & Remon. Washer South face 34" Oak
N35°W 50.09' Fnd Nail & Remon. Washer East face 24" Oak
N69°W 71.84' Fnd Nail & Remon. Washer South face 18" Oak
S71°W 60.93' Fnd Nail & Remon. Washer North face 26" Oak
S72°E 90.73' Fnd Nail & Remon. Washer North face 16" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date December 20, 1994