

Compliance with ACT 345, P.A. 1990

LAND CORNER RECORDATION CERTIFICATE APPROVED ON: 8-31-94
Filing Requirement of Act 74, Mich. P.A. 1970 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

For corners in

Oakland

(County)

Located In: Oxford Twp.

Corner Code #

1. Public Land Survey	T	5N	R	10E	A-2
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
24 OCT 94 8:48 A.M. RECEIPT# 33B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Register of Deeds Stamp & File Number

- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on July 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1818-GLO Wampler, D.S.; Set Post 7" White Oak N59°W 33 Links

1.) 1989-Kennedy, P.S. #17623; LCRC L.10869, Pg.250 - Fnd 1/2" Iron Rod

2.) 1975-Elrich, P.S. #18986; Survey L.6432, Pg.367 - Fnd

3.) 1992-Kennedy, P.S. #17623; Survey L.12467, Pg.735 - Fnd 1/2" Iron Rod, used same wit as 1989 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod that is located 8" under the road surface and 8' East of the center of Baldwin Road, which is gravel surface. There is a fence/tree line extending to the East.

Witnesses from LCRC #1 and Survey #2 were used to recover and verify the location of the found 1/2" Iron Rod.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.

S52°W 42.87' Set PK & Remon. Washer SE face 24" Oak

S41°E 65.75' Set PK & Remon. Washer NE face Power Pole

Due East 32.20' Set PK & Remon. Washer South face Guide Pole

N68°W 40.34' Set PK & Remon. Washer NE face 21" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by

Huston Kennedy

Date

September 1, 1994

Surveyor's Michigan License No.

17623

7.00
2.00
file