

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED ON: 8-31-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

For corners in

Oakland
(County)

Located In: Oxford
Twp.

Corner Code #

- 1. Public Land Survey T 5N R 10E A-5
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec S T R

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
24 OCT 94 8:48 A.M. RECEIPT# 339
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on August 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post; 10" Aspen N57°W 55 Links
- 1.) 1979-Kennedy, P.S. #17623; LCRC L.7417, Pg.487 - Fnd Iron in a Monument Box
- 2.) 1978-Kennedy, P.S. #17623; Unrecorded Survey - Fnd Iron in a Monument Box
- 3.) 1979-Kennedy, P.S. #17623; Unrecorded Survey - Fnd Iron in a Monument Box
- 4.) 1980-Kennedy, P.S. #17623; Unrecorded Survey - Fnd Iron in a Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Pipe in a Monument Box located in the centerline of Baldwin Road, which is bituminous surface, and the center of Hummer Lake Road to the East, which is gravel surface.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 1/2" Iron Pipe.

I accepted the found 1/2" Iron Pipe as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-5 I replaced the found 1/2" Iron Pipe with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, P.S. #17623 in a existing Monument Box.
- S84°W 31.81' Set PK & Remon. Washer North face 19" Oak
- S40°E 57.55' Set PK & Remon. Washer NE face Power Pole
- N67°E 47.31' Set PK & Remon. Washer SE face 29" Oak
- N27°E 132.74' Set PK & Remon. Washer NW face 31" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date September 1, 1994

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Rod in a Monument Box.

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

7.00
2.00
file