

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Compliance with ACT 345, P.A. 1990

For corners in

Oakland (County)

Located In: Oxford Twp. Corner Code # A-8

APPROVED ON: 8-31-94 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

- 1. Public Land Survey T 5N R 10E A-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
2 DEC 94 11:36 A.M. RECEIPT# 51B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
OK - T. SMITH
Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Cell (8,1) contains a dot.

I, Huston K. Kennedy, in a field survey on September 3, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post; White Oak S51\*W 18 Links; White Oak S80\*E 41 Links
1.) 1977-Kennedy, P.S. #17623; LCRC L.6965, Pg.93 - Fnd 1/2" Iron Rod in a Monument Box
2.) 1977-Kennedy, P.S. #17623; Survey L.6946, Pg.506 - Fnd 1/2" Iron Rod in a Monument Box, used same wit as 1977 LCRC

Handwritten signature/initials

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 5/8" Iron Rod in a Monument Box that is located 1.5' East of the centerline of Baldwin Road, which is bituminous surface. There is a tree and fence row extending to the East. The East 1/4 corner of Section 24, T5N, R9E, Brandon Township is located 287.83 feet to the North.

Witnesses from LCRC #1 were used to recover and verify the location of the found 5/8" Iron Rod in a Monument Box.

I accepted the found 5/8" Iron Rod in a Monument Box as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-8 I replaced the 5/8" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a existing Monument Box.
S39°W 49.37' Set PK & Remon. Washer SE face 24" Maple
S17°W 87.76' Set PK & Remon. Washer East face 9" Elm
N19°W 94.22' Set PK & Remon. Washer NE face 8" Oak
N85°E 31.91' Set PK & Remon. Washer West face Power Pole
North 287.83 feet East 1/4 corner of Section 24, T5N, R9E.

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date October 31, 1994