

LAND CORNER RECORDATION CERTIFICATE 7.00 MISCELLANEOUS RECORDING
Filing Requirement of Act 74, Mich. P.A. 1970 2.00 REMONUMENTATION

For corners in

Oakland
(County)

Located In: Oxford
Twp.

Corner Code #

- 1. Public Land Survey T 5N R 10E B-3
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

15 NOV 94 8:56 A.M. RECEIPT# 13B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 9-7-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
OK - T. SMITH

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3	7	8	9	10	11	12						
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on August 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post; 6" ? N12°E 20 Links; 8" Black Oak S20°W 70 Links
- 1.) 1979-Kennedy, P.S. #17623; LCRC L.7417, Pg.487 - Fnd P.K. Nail
- 2.) 1989-Kennedy, P.S. #17623; LCRC L.10869, Pg.250 - Fnd a #100 Nail
- 3.) 1974-Kennedy, P.S. #17623; Survey L.6293, Pg.718 - Fnd P.K. Nail, used same wit as 1979 LCRC
- 4.) 1975-Elrich, P.S. #18986; Survey L.6432, Pg.367 - Fnd P.K. Nail
- 5.) 1992-Kennedy, P.S. #17623; Survey L.12467, Pg.735 - Fnd #100 Nail, used same wit as 1989 LCRC
- 6.) 1977-Kennedy, P.S. #17623; Unrecorded Survey - Fnd P.K. Nail
- 7.) 1979-Kennedy, P.S. #17623; Unrecorded Survey - Fnd P.K. Nail
- 8.) 1979-Lippincott, P.S. #25855; Unrecorded Survey - Fnd P.K. Nail
- 9.) 1988-Kennedy, P.S. #17623; Unrecorded Survey - Fnd - #100 Nail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd #100 Spike located 0.5' North of the centerline of Oakwood Road, which is bituminous surface with a tree-fence line extending to the North.


Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found #100 Spike.

I accepted the found #100 Spike as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-3 I replaced the found #100 Spike with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a new Monument Box.
- S06° E 34.05' Set PK & Remon. Washer West face Power Pole
- S57° E 74.06' Set PK & Remon. Washer NE face Power Pole
- N82° E 98.37' Set PK & Remon. Washer South face 41" Oak
- N40° W 56.56' Set PK & Remon. Washer SW face 39" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date September 2, 1994