

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

Oakland (County)

Located In: Oxford Twp.

Corner Code # B-5

- 1. Public Land Survey T 5N R 10E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

\$ 7.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

24 OCT 94 8:49 A.M. RECEIPT# 338
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK REGISTER OF DEEDS

APPROVED ON: 8-31-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is marked at row 5, column B.

I, Huston K. Kennedy, in a field survey on August 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 18" White Oak N41°W 18 Links; 12" White Oak S58°E 46 Links
1.) 1979-Kennedy, P.S. #17623; LCRC L.7524, Pg.757 - Fnd 1/2" Iron rod
2.) 1975-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod
3.) 1978-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod
4.) 1989-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod

7.00 fee
2.00 fee

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994-Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod that is located 0.5" under the road surface and 5' South of the center of Hummer Lake Road, which is gravel surface and a tree line extending to the North and South.

Witnesses from LCRC #1 and Unrecorded Survey #4 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-5 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod diameter brass cap stamped Oakland County Remonumentation, PS #17623.
N06°W 13.30' Set PK & Remon. Washer SW face triple 12" Hickory
N40°E 29.54' Set PK & Remon. Washer SE face 14" Cherry
S07°W 24.76' Set PK & Remon. Washer West face 15" Oak
S37°W 34.57' Set PK & Remon. Washer SE face 18" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date September 1, 1994