

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for County (Oakland), Located In (Oxford Twp.), Corner Code (# B-7), and numbered sections 1-5 for Public Land Survey, Property Controlling, Miscellaneous, Lot No., and Private Claims.

OK - T. SMITH

Compliance with ACT 345, P.A. 1990

APPROVED ON: 8-31-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on August 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post; 8" Ash S14*W 57 Links
1.) 1979-Kennedy, P.S. #17623; LCRC L.7417, Pg.488 - Fnd 1/2" Iron Rod
2.) 1979-Kennedy, P.S. #17623; LCRC L.7524, Pg.757 - Fnd 1/2" Iron Rod, used same wit as 1979 LCRC
3.) 1985-Kennedy, P.S. #17623; LCRC L.9000, Pg.574 - Fnd 1/2" Iron Rod
4.) 1972-Kennedy, P.S. #17623; LCRC L.5904, Pg.35 - Fnd 1/2" Iron Rod
5.) 1976-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod
6.) 1977-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod
7.) 1979-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod
8.) 1984-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod
9.) 1987-Carlson, P.S. #9189; Unrecorded Survey - Fnd 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod that is located 3" under the road surface and 3' North of the center of Granger Road, which is gravel surface. There is a tree row extending to the North and South.

Witnesses from LCRC #3 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
2 NOV 94 9:09 A.M. RECEIPT# 13B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-7 I replaced the 1/2" Iron Rod with 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
S37°E 29.01' Set PK & Remon. Washer NE face 29" Ash
S11°E 19.25' Set PK & Remon. Washer East face 9" Elm
S76°W 95.01' Set PK & Remon. Washer North face 28" Ash
N38°E 22.33' Set PK & Remon. Washer NE face 6" Ash

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date September 1, 1994