

OK - T. SMITH

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland

(County)

Oxford
Located in Twp.

Corner Code #

- | | | | | | |
|------------------------------------|---|----|---|-----|-----|
| 1. Public Land Survey | T | 5N | R | 10E | C-1 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

24 OCT 94 8:49 A.M. RECEIPT# J3B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 8/31/94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on July 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post; 13" White Oak N65°E 7 Links; White Oak S47°W 40 Links
1.) 1985-Griggs, P.S. #23511; LCRC L.8914, Pg.607 - Set 1/2" Iron Rod
2.) 1975-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod
3.) 1993-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod that is location 6" under the road surface and 11' South of the center of Davison Lake Road, which is a gravel surface.

Witnesses from the Unrecorded Survey #2 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-1 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, P #17623.
S72°W 35.00' Set PK & Remon. Washer North face 12" Ash
S51°E 66.63' Set PK & Remon. Washer NE face 14" Maple
N42°W 48.87' Set PK & Remon. Washer SW face 32" Maple
N36°E 38.28' Set PK & Remon. Washer NW face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of position of the original corner.



Signed by Huston Kennedy
Surveyor's Michigan License No. 17623

Date September 1, 1994

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

7.00
2.00
file