

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
APPROVED ON: 9-7-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

For corners in
Oakland
(County)

Located In: Oxford Twp. Corner Code #

1. Public Land Survey	T 5N	R 10E	C-8
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
25 OCT 94 8:33 A.M. RECEIPT# 44B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Huston K. Kennedy, in a field survey on August 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1817-GLO Wampler, D.S.; Set Post; 12" Black Oak N41°E 95 Links; 12" Black Oak S61°W 156 Links
 - 1.) 1974-Kennedy, P.S. #17623; LCRC L.6383, Pg.881 - Fnd 1/2" Iron Rod
 - 2.) 1979-Kennedy, P.S. #17623; LCRC L.7417, Pg.488 - Fnd 1/2" Iron Rod
 - 3.) 1985-Kennedy, P.S. #17623; LCRC L.9000, Pg.574 - Fnd 1/2" Iron Rod
 - 4.) 1965-Kieft Engineering; Unrecorded Survey - Fnd 3/4" Pinched Iron
 - 5.) 1974-Kennedy, P.S. #17623; Unrecorded Notes - Fnd 1/2" Iron Rod
 - 6.) 1979-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod
 - 7.) 1984-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod
 - 8.) 1986-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod
 - 9.) 1992-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod that is located 5" under the road surface and 1' West of the center of Coats Road, which is gravel surface with a tree line extending to the East & West.

Witnesses from LCRC #1, 2 & 3 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- C-8 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.
- N37°E 140.42' Set PK & Remon. Washer SW face Power Pole
 - N42°W 39.62' Set PK & Remon. Washer NE face 19" Oak
 - S17°E 78.41' Set PK & Remon. Washer West face 11" Walnut
 - S87°E 56.91' Set PK & Remon. Washer North face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date September 1, 1994