

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED ON: 9-7-94 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

For corners in

Form with fields for County (Oakland), Located In (Oxford Twp.), Corner Code (# C-9), and numbered sections 1-5 for survey details.

\$ 7.00 MISCELLANEOUS RECORDING \$ 2.00 REMONUMENTATION 25 OCT 94 8:33 A.M. RECEIPT# 448 PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on August 10, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 24" White Oak N75°E 35 Links
1.) 1974-Kennedy, P.S. #17623; L.6383, Pg.881 - Fnd 3/4" Iron Pipe
2.) 1976-Kennedy, P.S. #17623; L.6821, Pg.466 - Fnd 3/4" Iron Pipe, used same wit as 1974 LCRC
3.) 1979-Kennedy, P.S. #17623; L.7417, Pg.488 - Fnd 3/4" Iron Pipe
4.) 1979-Lippincott, P.S. #25855; LCRC L.7447, Pg.198 - Fnd 1" Iron Pipe
5.) 1988-Kennedy, P.S. #17623; LCRC L.10709, Pg.791 - Fnd
6.) 1976-Kennedy, P.S. #17623; Survey L.6717, Pg.301 - Fnd 3/4" Iron Pipe, used same wit as 1974 LCRC
7.) 1979-Kennedy, P.S. #17623; Survey L.7426, Pg.886 & 887 - Set 3/4" x 20" Iron Pipe, used same wit as 1974 LCRC
8.) Kieft Engineering; Unrecorded Notes - Iron Pipe
9.) 1974-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 3/4" Iron Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" Iron Pipe in a Monument Box located in the centerline of Seymour Lake Road, which is bituminous surface, and in the center of Coats Road, which is gravel surface.

Witnesses from LCRC #1 & 4 were used to recover and verify the location of the 3/4" Iron Pipe in a Monument Box.

I accepted the found 3/4" Iron Pipe in a Monument Box as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 I replaced the found 3/4" Iron Pipe with a 5/8" x 24" Iron Rod w/2" brass cap stamped Oakland County Remonumentation, PS, #17623 in a existing Monument Box.
S42°W 59.31' Set PK & Remon. Washer SE face Power Pole
S44°E 76.82' Set PK & Remon. Washer SW face Power Pole
N47°W 50.16' Set PK & Remon. Washer SW face Power Pole
N67°E 140.73' Set PK & Remon. Washer South face Guide Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature] Date September 1, 1994
Surveyor's Michigan License No. 17623