

Nov 15 94 295375

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Compliance with ACT 345, P.A. 1990

APPROVED ON: 9-7-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
15 NOV 94 8:56 A.M. RECEIPT# 13B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

Table with columns: Oakland (County), Located In: Oxford Twp., Corner Code #, and survey details for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. , Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on August 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post 18" White Oak S84°E 81 Links; 24" Black Oak N45°E 142 Links
1.) 1973-Feldhauser, P.S. #10685; LCRC L.6060, Pg.14 - Fnd 5/8" Iron Rod
2.) 1973-Feldhauser, P.S. #10685; LCRC L.6156, Pg.680 - Fnd Iron, used same wit as 1973 LCRC
3.) 1977-Kennedy, P.S. #17623; LCRC L.7067, Pg.314 - Fnd P.K. Nail
4.) 1982-Kennedy, P.S. #17623; LCRC L.8132, Pg.538 - Fnd 1" Pinched Iron Rod
5.) 1973-Feldhauser, P.S. #10685; Survey L.6156, Pg.676 - Fnd
6.) 1974-Elrich, P.S. #18986; Survey L.6226, Pg.709 - Fnd Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" Iron Bolt Spike 3" under the road surface and 6.77' North of the centerline of Oakwood Road, which is bituminous surface. A tree row extending to the North.

Witnesses from LCRC #1 & 3 were used to recover and verify the location of the found 3/4" Iron Bolt Spike.

I accepted the found 3/4" Iron Bolt Spike as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-3 I replaced the found 3/4" Iron Bolt Spike with 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a new Monument Box.
S06°W 38.44' Set PK & Remon. Washer West face Power Pole
S49°E 98.87' Set PK & Remon. Washer NE face Power Pole
N12°E 22.76' Set PK & Remon. Washer West face 27" Oak
N38°W 36.13' Set PK & Remon. Washer SW face clump of 10" Basswoods

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date September 14, 1994

