

OCT 24 94 278812

LIBER 15053 PG 069

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in
Oakland
(County)

Located In: Oxford Twp. Corner Code #

Table with 3 columns: Item description, Survey details (T, R, S, T, R, S, T, R), and Corner Code #. Includes items like Public Land Survey, Property Controlling in Section, etc.

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
24 OCT 94 8:50 A.M. RECEIPT# 338
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
ACT 345, P.A. 1990

APPROVED ON: [Signature]
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is marked in the cell corresponding to column E and row 5.

I, Huston K. Kennedy, in a field survey on July 25, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1818-GLO Wampler, D.S.; Set Post on the Township line 10 Links East of Post 24" White Oak S24*E 94 Links

- 1.) 1984-Kennedy, P.S. #17623; LCRC L.8599, Pg.134 - Fnd "T" Iron
2.) 1977-Henderson, P.S. #16043; Survey L.6845, Pgs.387-388 - Fnd "T" Iron
3.) 1978-Henderson, P.S. #16043; Survey L.7300, Pgs.661-665 - Fnd "T" Iron
4.) 1979-Smith, P.S. #21582; Survey L.7593, Pg.322 - Fnd
5.) 1990-Smith, P.S. #21582; Survey L.11300, Pgs.303-304 - Fnd
6.) 1980-Smith, P.S. #21582; Unrecorded Survey - Fnd Iron
7.) 1984-Kennedy, P.S. #17623; Unrecorded Survey - Fnd "T" Iron
8.) 1992-Kennedy, P.S. #17623; Unrecorded Survey - Fnd "T" Iron
9.) 1993-Kennedy, P.S. #17623; Unrecorded Survey - Fnd "T" Iron

Handwritten notes: 7.00, 2.00, [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd "T" Iron that is located 9" under the road surface and located at the intersection of the center of Thomas Road and Davison Lake Road, which are both gravel surfaces.

Witnesses from LCRC #1 were used to recover and verify the location of the found "T" Iron.

I accepted the found "T" Iron as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 I replaced the found "T" Iron with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, P.S. #17623.

- S47°E 40.25' Set PK & Remon. Washer SW face 32" Oak
N43°E 45.13' Set PK & Remon. Washer SE face Power Pole
S44°W 48.35' Set PK & Remon. Washer NW face 33" Maple
N54°W 71.17' Set PK & Remon. Washer SW face 21" Box Elder

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date September 9, 1994