

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (County)

Located In: Oxford Twp.

Corner Code --

- 1. Public Land Survey T 5N R 10E E-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
24 OCT 94 8:50 A.M. RECEIPT# 338
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance with ACT 345, P.A. 1990

APPROVED ON: 9-7-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column D and row 7.

I, Huston K. Kennedy, in a field survey on July 25, 1994, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post 12" White Oak N05*W 13 Links; 12" White Oak S36*B 5 Links
1.) 1974-Henderson, P.S. #16043; LCRC L.6225, Pg.713 - Set 1/2" Re-rod
2.) 1989-Buckerfield, P.S. #10868; LCRC L.11138, Pg.759 - Fnd 1/2" Iron Rod
3.) Oakland County Road Commission; Unrecorded Survey - Fnd Reinforced Iron
4.) 1992-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod
5.) 1992-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod

Handwritten note: 7.00 Paid, 2.00 file

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod that is 4" under the road surface and 7' East center of Dunlap Road to the North, and in the center of Granger Road to the South and in the center of Granger Road to the West. Both are gravel surface roads.

Witnesses from LCRC #1 and the Unrecorded Surveys #4 & 5 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" Brass cap stamped Oakland County Remonumentation PS #17623.

- N36°W 75.76' Set PK & Remon. Washer SW face 26" Oak
Due East 48.37' Set PK & Remon. Washer South face 17" Cherry
S42°E 57.83' Set PK & Remon. Washer NE face 8" Oak
S40°W 64.48' Set PK & Remon. Washer SE face 29" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]

Date September 8, 1994

Surveyor's Michigan License No. 17623