

Nov 29 286573

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Compliance with ACT 345, P.A. 1990

For corners in

Table with columns: Oakland (County), Located In: Oxford Twp., Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

APPROVED ON: 9-7-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
2 NOV 94 9:09 A.M. RECEIPT# 13B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
OK - T. SMITH
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-K and rows 2-12. A dot is marked at the intersection of column C and row 8.

I, Huston K. Kennedy, in a field survey on August 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post 12" White Oak N30*W 36 Links; 12" White Oak S41*E 84 Links
1.) 1986-Kennedy, P.S. #17623; LCRC L.9521, Pg.82 - Fnd 3/4" Iron Pipe
2.) 1989-Buckerfield, P.S. #10868; LCRC L.11138, Pg.760 - Fnd 1/2" Iron Rod
3.) 1992-DeDecker, P.S. #8386; LCRC 12649, Pg.825 - Fnd a Pipe
4.) 1988-Kennedy, P.S. #17623; Survey L.10340, Pgs.571-573 - Fnd 1/2" Iron Pipe, used same wit as 1986 LCRC
5.) Oakland County Road Commission; Unrecorded Witnesses - Fnd Iron Pipe.
6.) 1986-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 3/4" Iron Pipe
7.) 1986-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 3/4" Iron Pipe
8.) 1992-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Pipe
9.) 1992-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Pipe that is 3" under the road surface and in the center of Granger Road extending to the North & South, which has a gravel surface with a gravel pit on the East and West side. Also found a second 1/2" Iron Rod 8.35' to the South.

Witnesses from LCRC #1, 2 & 3 were used to recover and verify the location of the found 1/2" Iron Pipe.

I accepted the found 1/2" Iron Pipe as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-8 I replaced the found 1/2" Iron Pipe with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.
S27°W 69.59' Set PK & Remon. Washer SE face 31" Maple
S46°W 40.46' Set PK & Remon. Washer SE face 28" Maple Oak
S48°E 54.57' Set PK & Remon. Washer SW face Power Pole
N66°E 44.12' Set PK & Remon. Washer NW face 32" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date September 9, 1994