

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

Table with columns: Oakland (County), Located In: Oxford Twp., Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
24 OCT 94 8:50 A.M. RECEIPT# 338
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance with ACT 345, P.A. 1990

APPROVED ON: 9-7-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-K and rows 1-13. A dot is marked at the intersection of column F and row 2.

I, Huston K. Kennedy in a field survey on August 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post 12" White Oak N51°E 40 Links; 18" White Oak S48°W 68 Links
1.) 1984-Kennedy, P.S. #17623; LCRC L.8599, Pg.134 - Fnd Iron Pipe
2.) 1977-Henderson, P.S. #16043; Survey L.6845, Pg.387 - Fnd 1" Iron Pipe
3.) 1978-Bates, P.S. #16699; Survey L.7300, Pg.654 - Fnd 1" Iron Pipe
4.) 1978-Elrich, P.S. #18986; Survey L.7300, Pg.661 - Fnd 1" Iron Pipe, used same wit as 1978 Survey
5.) 1990-Smith, P.S. #21852; Survey L.11300, Pg.303 - Fnd
6.) 1956-Oakland County Road Commission - Set 1/2" Iron Rod
7.) 10984-Kennedy, P.S. #17623; Unrecorded Survey - Fnd Iron Pipe

7.00
2.00
file

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1" Iron Pipe that is located 3" under the road surface and 8' South of the center of Davison Lake Road, which is gravel surface. The North 1/4 corner Section 4 is also the point of beginning for "DAVISON LAKE FARMS" a plat recorded in Liber 158, on pages 26 & 27 of Oakland County Records.

Witnesses from LCRC #1, Surveys #3 & 5 were used to recover and verify the location of the found 1" Iron Pipe.

I accepted the found 1" Iron Pipe as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-1 I replaced the found 1" Iron Pipe with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, P.S. #17623.
N42°E 49.45' Set PK & Remon. Washer SE face 42" Oak
N38°W 44.67' Set PK & Remon. Washer SW face 10" Oak
S07°E 15.41' Set PK & Remon. Washer West face 8" Box Elder
S47°E 35.45' Set PK & Remon. Washer North face 9" Cherry

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature] Date September 8, 1994
Surveyor's Michigan License No. 17623