

LISER 15527 pg 255

COPY

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland
(County)

Located In: Oxford Twp. Corner Code #

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
19 JUL 95 9:33 A.M. RECEIPT# 8A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 7-12-95 Tom S.
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 1. Public Land Survey T 5 N R 10 E F-7
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|
| A | B | C | D | E | F | G | H | I | J | K | L |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 |
| 3 | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 |
| 5 | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 |
| 7 | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 |
| 9 | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 |
| 11 | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 |
| 13 | | | | | | | | | | | |

I, Huston K. Kennedy, in a field survey on June 14, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1818-GLO Wampler, D.S.; Set Post 10" White Oak N52°W 8 Links; 10" White Oak S72 1/2°E 36 Links
Nothing has been recorded for this corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - I recovered the corner (G-7) at the midpoint on a straight line between E-7 and G-7.

FIELD MEASUREMENTS BETWEEN

- E-7 to G-7 5661.16 Ft., GLO = 80 chains or 5280.00 Ft.
- E-7 to F-7 2830.58 Ft., GLO = 40 chains or 2640.00 Ft.
- F-7 to G-7 2830.58 Ft., GLO = 40 chains or 2640.00 Ft.

7.00
2.00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
F-7 I set a 1/2" Iron Rod encased in a 4" concrete cylinder 36" long w/2" diameter brass cap stamped Oakland County Remonumentation PS #17623
S76°W 260.32' Set PK & Remon. Washer North face 8" Poplar
S83°W 323.32' Set PK & Remon. Washer South face 12" Poplar
N39°W 284.38' Set PK & Remon. Washer NE face 10" Poplar
N48°W 254.34' Set PK & Remon. Washer NE face 12" Poplar

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date July 13, 1995

