

JUL 1995 128593

LIBER 15527-256

COPY

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland (County)

Located In: Oxford Twp. Corner Code #

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
19 JUL 95 9:33 A.M. RECEIPT# 8A
PAID RECORDED - OAKLAND COUNTY
LYNN B. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 7-12-95 Tom S.
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

| | | | | | |
|--------------------------------------|---|------------|---|-------------|------|
| 1. Public Land Survey | T | <u>5</u> N | R | <u>10</u> E | F-13 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Section | S | | T | R | |
| | S | | T | R | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|----|----|----|----|----|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | | | | | | |
| 3 | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | |
| 5 | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | |
| 7 | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | |
| 9 | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | |
| 11 | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | |
| 13 | | | | | | | | | | | |

I, Huston K. Kennedy, in a field survey on June 14, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1818-GLO Wampler, D.S.; Set Post 10" White Oak N88°E 24 Links; 8" White Oak S53°W 31 Links
Nothing has been recorded for this corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - I set with a 1/2" Iron Rod encased in a 4" diameter concrete cylinder 36" long with 2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 at the midpoint on a line between the Southwest and Southeast corner of Section 33.

FIELD MEASUREMENTS BETWEEN

E-13 to G-13 5246.18 Ft., GLO = 80 chains or 5240.00 Ft.
E-13 to F-13 2623.09 Ft., GLO = 40 chains or 2640.00 Ft.
G-13 to G-13 2623.09 Ft., GLO = 40 chains or 2640.00 Ft.

7.00
2.00
Rmk

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 I set a 1/2" Iron Rod encased in a 4" diameter Concrete cylinder 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
S04°W 19.29' Fnd PK & Remon. Washer East face 14" Pine
S10°E 34.50' Fnd PK & Remon. Washer East face 10" Pine
S38°E 30.20' Fnd PK & Remon. Washer West face 10" Pine
N08°E 37.79' Fnd PK & Remon. Washer West face 18" triple Cherry

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date July 13, 1995

