

MAY 16 1996

COMMISSION

695218286

15796-532
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland
(County)

Located in: Oxford Twp. Corner Code #

- 1. Public Land Survey T 5N R 10E G-7
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
6 NOV 95 9:01 A.M. RECEIPT# 8A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, REGISTER OF DEEDS

APPROVED ON: 10-2-95
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on August 10, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1818-GLO Wampler, D.S.; Post not set, falls in a lake
Nothing has been recorded for this corner

I have no personal history of any surveying being done in this area due to the mining operation. James Buckerfield, PS #10656 made a survey for all of American Aggregates property lying West of M-24 Highway and South of Dunlap Road in April of 1988.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - I set two reference corners for G-7, I set a 1/2" Iron Rod encased in a 4" diameter concrete cylinder 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 on the straight line between G-6 and G-7 470.00 feet South of G-7, and is located 10 feet ± South of the water's edge of Stoney Lake, also I set a 1/2" Iron Rod encased in a 4" diameter concrete cylinder 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 on the straight line between G-7 and H-7 373.00 feet East of G-7 and is located 71 feet ± East of the water's edge of Stoney Lake.

FIELD MEASUREMENTS BETWEEN

- G-7 to F-7 2803.58 Ft., GLO = 40 chains or 2640.00 Ft.
- G-7 to G-6 2284.50 Ft., GLO = 40 chains or 2640.00 Ft.
- G-7 to H-7 2224.12 Ft., GLO = 33.50 + 6.50 chains or 2640.00 Ft.
- G-7 to G-8 3146.30 Ft., GLO = 37.50 + 2.50 chains or 2640.00 Ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-7 I placed 4" diameter concrete cylinder 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
- Reference corner to the South
S30°E 26.59' Set PK & Remon. Washer NE face 13" Poplar
S27°W 30.05' Set PK & Remon. Washer SE face 17" Poplar
S76°W 67.14' Set PK & Remon. Washer SE face 11" Poplar
S84°W 79.93' Set PK & Remon. Washer South face 12" Poplar
- Reference corner to the East
S22°W 73.12' Set PK & Remon. Washer NW face 12" Maple
S41°W 54.46' Set PK & Remon. Washer NW face 14" Maple
N27°W 94.86' Set PK & Remon. Washer SW face 32" Poplar
N13°E 111.70' Set PK & Remon. Washer East face Power Pole

The selected location for these reference corners are accepted as a careful and faithful determination of the location as indicated

Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date October 10, 1995

