

LIBER 15527 PG 257

JUL 1995 128594

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COPY

For corners in Oakland  
(County)

Located In: Oxford Twp. Corner Code # \_\_\_\_\_

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
19 JUL 95 9:33 A.M. RECEIPT# 8A  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 7-12-95 Tom S.  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- |                                      |              |               |            |
|--------------------------------------|--------------|---------------|------------|
| 1. Public Land Survey                | T <u>5</u> N | R <u>10</u> E | <u>G-8</u> |
|                                      | T _____      | R _____       | _____      |
|                                      | T _____      | R _____       | _____      |
|                                      | T _____      | R _____       | _____      |
| 2. Property Controlling in Section   | S _____      | T _____       | R _____    |
|                                      | S _____      | T _____       | R _____    |
| 3. Miscellaneous Property in Section | S _____      | T _____       | R _____    |
|                                      | S _____      | T _____       | R _____    |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2					
3										
4	7	8	9	10	11					
5										
6	18	17	16	15	14					
7										
8	19	20	21	22	23	24				
9										
10	30	29	28	27	26	25				
11										
12	31	32	33	34	35	36				
13										

I, Huston K. Kennedy in a field survey on June 14, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1818-GLO Wampler, D.S.; Set Post 12" White Oak N57°W 47 Links; 8" Black Oak S62°E 43 Links  
Nothing has been recorded for this corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - I recovered the corner (G-8) at the midpoint on a straight line between G-7 and G-9. When the survey crew was setting the concrete monument at the corner they dug through an old road bed. Dunlap Road did extend from Granger Road East to W-24 Highway in the early 1950's, however, Dunlap Road was vacated and relocated to the North.

FIELD MEASUREMENTS BETWEEN

- G-7 to G-9 6292.60 Ft., GLO = 80 chains or 5280.00 Ft.
- G-7 to G-8 3146.30 Ft., GLO = 40 chains or 2640.00 Ft.
- G-8 to G-9 3146.30 Ft., GLO = 40 chains or 2640.00 Ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 I set a 1/2" Iron Rod encased in a 4" concrete cylinder 36" long w/2" diameter brass cap stamped Oakland County Remonumentation PS #17623  
N81°W 105.56' Set PK & Remon. Washer South face 7" Poplar  
N74°W 71.39' Set PK & Remon. Washer SW face 10" Poplar  
N22°W 39.76' Set PK & Remon. Washer NE face 6" Poplar  
N52°E 178.89' Set PK & Remon. Washer NW face 8" Poplar

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence position of the original corner.

Signed by [Signature]

Date July 13, 1995

Surveyor's Michigan License No. 17623

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 1, 1988

