

JUL 1995 128595

RISER 15527rc258

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland (County)

Located In: Oxford Twp. Corner Code #

- 1. Public Land Survey T 5 N R 10 E G-12
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
19 JUL 95 9:34 A.M. RECEIPT# 8A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance with ACT 345, P.A. 1990
APPROVED ON: 7-12-95 Tam S.
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on June 15, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1818-GLO Wampler, D.S.; Set Post 6" Black Oak N05°E 187 Links
1.) Patterson, PS #17631; LCRC L.14902, Pg.762 - Auxiliary corner to G-12

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - I could not recover the auxiliary corner to G-12 as per the LCRC. I set a point at the midpoint on a straight line between (G-11 & G-13) 4753.48 Ft. = 2376.75 Ft., the corner is a lake.

I set a reference corner on the line between Sections 33 & 34, 100.00 feet North of the corner (G-12).

FIELD MEASUREMENTS BETWEEN

G-11 to G-12 2376.74 Ft., GLO = 40 chains or 2640.00 Ft.
G-12 to G-13 2376.74 Ft., GLO = 40 chains or 2640.00 Ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 I set a 1/2" x 60" Iron Pipe w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 as a reference corner the line between Sections 33 & 34, 100.00 feet North of the corner (G-12)
N12°W 42.50' Set PK & Remon. Washer East face 5" Poplar
N05°W 73.08' Set PK & Remon. Washer East face 7" Cherry
N10°E 70.70' Set PK & Remon. Washer NW face 10" Cherry
N11°E 57.72' Set PK & Remon. Washer NW face 7" Poplar

The selected location for this reference corner is accepted as a careful and faithful determination of the position as indicated

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date July 13, 1995



7.00
2.00
PK

Grid table with columns A-K and rows 2-13, containing numbers 6-36 and a dot at row 12, column G.