

LIBER 14960 PG 112

94 242442

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in  
Oakland  
(County)

Located In: Oxford Corner Code H-1  
Township

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
8 SEP 94 3:19 P.M. RECEIPT# 134B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

1. Public Land Survey	T	5	N	R	10	E	H-1
	T			R			
	T			R			
	T			R			
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-29-93  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on November 4, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	13		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817 GLO - Wampler, D.S.; Post set; No witnesses  
1980 Pangus, P.S. #21578; LCRC L.7859, Pg.427-428 - Fnd 1/2" iron rod.

*Handwritten initials/signature*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Huston Kennedy, P.S. #17623 - Fnd 1/2" iron rod 3' South of the center of Davison Lake Road, which is gravel.  
Only one witness point from the LCRC is still existing. It was used to recover and verify the found 1/2" iron rod.

I accepted the found 1/2" iron rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1 I replaced the found 1/2" iron rod with a 5/8" x 24" iron rod with a 2" diameter cap stamped Oakland County Remonumentation P.S. #17623.

S75°E-59.50 ft-Set PK/Remon. Tag NE face 22" Elm  
S18°E-22.82 ft-Set PK/Remon. Tag NE face 18" Oak  
S80°W-106.66 ft-Set PK/Remon. Tag North face 20" & 21" Twin Oak  
N24°E-42.67 ft-Set PK/Remon. Tag West face 18" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original position.

Signed by Huston K. Kennedy  
Surveyor's Michigan License No. 17623

Date March 23, 1994

