

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

Oakland (County)

Located in: Oxford Twp.

Corner Code #

- 1. Public Land Survey T 5N R 10E H-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
24 OCT 94 8:51 A.M. RECEIPT# 33B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
ACT 345, P.A. 1990

APPROVED ON: 27 94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column G and row 7.

I, Huston K. Kennedy, in a field survey on September 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post; 12" White Oak N86*W 25 Links; 12" White Oak S68*E 29 Links
1.) 1979-Buckerfield, P.S. #10868; LCRC. L.7508, Pg.677 - Fnd 1" Pipe
2.) 1989-Buckerfield, P.S. #10868; LCRC L.11138, Pg.758 - Fnd 3/4" Iron Pipe
3.) 1985-Sandomierskie, P.S. #24616; Unrecorded Survey - Fnd 3/4" Pipe
4.) 1992-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1" Iron Pipe

7.00
2.00
file

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1" Iron Pipe that is located 4" under the road surface and in the center of Ray Road which is gravel surface.

Witnesses from LCRC #1 and Unrecord Surveys #2 & 4 were used to recover and verify the location of the found 1" Iron Pipe.

I accepted the found 1" Iron Pipe as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 I replaced the found 1" Iron Pipe with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, P.S. #17623.

- N23° E 42.15' Set PK & Remon. Washer NW face 12" Pine
N18° W 42.80' 8" Steel Gate Post
S16° E 62.07' Set PK & Remon. Washer NE face 12" Elm
S77° W 86.17' Set PK & Remon. Washer North face clump 10" Elm

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date September 7, 1994