

LAND CORNER RECORDATION CERTIFICATE 7.00 MISCELLANEOUS RECORDING
Filing Requirement of Act 74, Mich. P.A. 1970 2.00 REMONUMENTATION

For corners in

Oakland
(County)

Located in: Oxford
Twp.

Corner Code #

20 JAN 95 7:34 A.M. RECEIPT# 8B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

- 1. Public Land Survey T 5N R 10E H-9
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-14-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Huston K. Kennedy, in a field survey on December 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post 10" White Oak N51°W 9 Links; 10" White Oak S23°W 51 Links
1.) 1982-Kennedy, P.S. #17623; LCRC L.8273, Pg.792 - Fnd P.K. Nail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd P.K. Nail in the centerline of Burdick Street, which has a bituminous surface over a concrete base, and Pontiac Street extending to the South, which has a bituminous surface. "Assessor's Plat No. 3" a pla recorded in Liber 42 of Plats, on page 21 of Oakland County Records is tied to the North 1/4 corner of Section 27. The P.K. Nail is 0.45 feet West of the sanitary sewer rim.

Witnesses from LCRC #1 were used to recover and verify the location of the found P.K. Nail.

I accept the found P.K. Nail as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

- H-9 to H-10 2704.61 Ft. (H. Kennedy 1992)
- H-9 to I-9 2468.25 Ft. (H. Kennedy 1994)
- H-9 to G-9 2468.54 Ft. (H. Kennedy 1990)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9 I replaced the found P.K. Nail with a 1/2" x 6" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.
S78°W 93.66' Set PK & Remon. Washer North face 16" Maple
N67°W 61.08' Set PK & Remon. Washer SW face 29" Maple
N72°E 71.82' Set PK & Remon. Washer South face 15" Maple
S72°E 79.95' Set PK & Remon. Washer North face 15" Maple

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]

Date December 15, 1994

Surveyor's Michigan License No. 17623