

COPY

JUL 1995 128596

15527PC259

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970... RECEIPT# 8A PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in Oakland (County)

Located In: Oxford Twp. Corner Code #

- 1. Public Land Survey T 5 N R 10 E H-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on June 15, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: 1818-GLO Wampler, D.S.; A post was not set at the corner, the corner was in a lake 1.) 1994-Patterson, PS #17631; LCRC L.14902, Pg.761 - Did not accept

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Corner now falls in a lake.

Point was computed on a straight line between the Southwest corner of Section 34 (G-13) and the South 1/4 corner of Section 3 (J-13), the distance between G-13 to J-13 is 7872.90 feet or 7872.90 Ft. = 2624.30, the corner does fall in a Lake.

The North 1/4 corner of Section 3, (H-1) T4N, R10E, was used as a reference corner to (H-13). The reference corner is South 82°21'19" West 228.66 feet from North 1/4 corner of Section 3 (H-1) is located 227.75 feet East along the township line and 20.3 feet North of the township line.

FIELD MEASUREMENTS BETWEEN G-13 to J-13 7872.90 Ft., GLO = 120 chains or 7920.00 Ft. G-13 to H-13 2624.30 Ft., GLO = 40 chains or 2640.00 Ft. H-13 to J-13 5248.60 Ft., GLO = 80 chains or 2640.00 Ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: H-13 I set a 5/8" x 60" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 as a reference corner to H-13 and located it N82°21'19" East 228.66 feet. S01°W 6.63' Set PK & Remon. Washer West face 8" Poplar S36°W 16.71' Set PK & Remon. Washer SE face 9" Poplar Due West 7.38' Set PK & Remon. Washer South face 10" clump Birch N26°W 18.46' Set PK & Remon. Washer NE face 10" Willow N82°21'19" East 228.66 feet North 1/4 corner of Sec 3, T4N, R10E, Orion Twp., (H-1)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date July 13, 1995



Grid table with columns A-L and rows 2-13. Contains numerical values for each cell, likely representing a survey grid or section numbers.