

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

Oakland

(County)

Located in: Oxford Township

Corner Code =#

Table with 3 columns: Description, Township, Corner Code. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
8 SEP 94 3:19 P.M. RECEIPT# 1349
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance with ACT 345, P.A. 1999

APPROVED ON: 12-29-93
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on November 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817 GLO - Wampler, D.S.; Set post; Beech N21°W 0.42 lks.; Beech S05°E 0.17 lks.
1980 Pangus, P.S. #21578; LCRC L.7859, Pg.427-428 - Fnd 1/2" iron rod
1982 Kennedy, P.S. #17623; LCRC L.8132, Pg.544 - Fnd 1/2" iron rod
1986 Gravlin, P.S. #23510; Survey L.9373, Pg.155-156 - Fnd 1/2" iron rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Huston Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod 4' South of the center of Davison Lake Road and 4' East of the center of Gardner Road to the North. Both are gravel roads.
One witness point from the 1980 LCRC is still existing, and it was used to recover and verify the found 1/2" Iron Rod. The other witness trees have been destroyed

I accepted the found 1/2" iron rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 I replaced the found 1/2" iron rod with a 5/8" x 24" iron rod with a 2" diameter cap stamped Oakland County Remonumentation P.S. #17623.

- N57°E-51.41 ft-Set PK/Remon. Tag SE face 15" & 18" Twin Oak
N47°W-48.25 ft-Set PK/Remon. Tag SW face 24" Apple
Due South-36.46 ft-Set PK/Remon. Tag East face 15" & 16" Twin Oak
S25°E-18.65 ft-Set PK/Remon. Tag SW face 19" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original position.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date March 23, 1994

