

COPY

LIBER 15517 PC 410

JUN 14 1995 12 52 42

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 \$ 7.00

For corners in Oakland (County)

Located In: Oxford Twp. Corner Code #

MISCELLANEOUS RECORDING \$ 2.00
REMONUMENTATION
14 JUL 95 8:38 A.M. RECEIPT# 9B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

- 1. Public Land Survey T 5N R 10E I-12
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

Compliance with ACT 345, P.A. 1990

APPROVED ON: 6-14-95 Toms
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	6	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Huston K. Kennedy, in a field survey on April 26, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1818-GLO Wampler, D.S.; Set Post 15" Black Oak N36°E 102 Links
1.) 1973-Lester, PS #18998; LCRC L.6028, Pg.641 - Fnd 1/2" Pipe
2.) 1994-Kennedy, PS #17623; LCRC L. 14419, Pg.398- Fnd 1/2" Iron Rod
3.) 1990-Kennedy, PS #17623; Unrecorded Survey - Fnd 1/2" Iron Rod, used same wit as 1994 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod 12" below surface. A tree-fence row extending to the North, South East & West.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

I-12 to I-11 2407.47 Ft., GLO = 40 chains or 2640.00 Ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-12 I replaced the found 1/2" Iron Rod with a 1/2" Iron Rod encased in a 4" diameter concrete cylinder 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
N02°W 33.19' Set PK & Remon. Washer East face 13" Oak
S88°W 24.60' Set PK & Remon. Washer North face 20" Oak
Due South 27.29' Set PK & Remon. Washer East face 27" Oak
S88°E 12.50' Set PK & Remon. Washer North face 12" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date June 14, 1995



7.00
2.00 (K)