

OK - T. SMITH

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland (County)

Located In: Oxford Twp.

Corner Code -#

- 1. Public Land Survey T 5N R 10E J-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
24 OCT 94 8:51 A.M. RECEIPT# 33B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
ACT 345, P.A. 1990
APPROVED ON: 9-7-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on August 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post; 10" White Oak S20\*W 15 Links; 10" White Oak N38 1/2 \*E 1.88 Links
1.) 1975-Kennedy, P.S. #17623; LCRC L.6414, Pg.19 - Fnd 3/4" Iron Pipe
2.) 1975-Heil, P.S. #18993; LCRC L.6587, Pg.371 - Fnd 1/2" Iron Rod
3.) 1982-Henderson, P.S. #16043; LCRC L.8153, Pg.440 - Fnd 1/2" Iron Rod in a Monument Box
4.) 1982-Kennedy, P.S. #17623; LCRC L.8190, Pg.68 - Fnd 1/2" Iron Rod in a Monument Box
5.) 1974-Kennedy, P.S. #17623; Survey L.6278, Pgs.791-792 - Fnd 1/2" Iron Rod, used same wit as 1975 LCRC
6.) 1982-Henderson, P.S. #16043; Survey L.8153, Pg.439 - Fnd 1/2" Iron Rod in a Monument Box, use same wit as 1982 LCRC
7.) 1985-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod in a Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod in a Monument Box that is located in the centerline of Oxford Road to the North which is bituminous surface, and in the centerline of Ray Road to the West, which is bituminous surface and Ray Road to the East, which has a gravel surface.

Witnesses from LCRC #1, 2 & 3 were used to recover and verify the found 1/2" Iron Rod in a Monument Box.

I accepted the found 1/2" Iron Rod in a Monument Box as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-7 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter cap stamped Oakland County Remonumentation, P.S. #17623 in a existing Monument Box.
N52°E 81.63' Set PK & Remon. Washer NW face Power Pole
S71°W 64.76' Set PK & Remon. Washer NW face 12" Walnut
S31°W 40.94' Set PK & Remon. Washer NW face 26" Walnut
S66°E 86.96' Set PK & Remon. Washer SW face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 623

Date September 8, 1994

