

JAN 20 95 01 11 92

LIBER 15212 PG 878

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in
Oakland
(County)

Located in: Oxford
Twp. Corner Code #

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
20 JAN 95 7:34 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-14-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 1. Public Land Survey T 5N R 10E J-9
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on December 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

- GLO Notes - No post set - No bearing trees
- 1.) 1989-Buckerfield, P.S. #10868; LCRC L.10887, Pg.472 - End 1" Pipe
- 2.) 1992-Heil, P.S. #18993; LCRC L.12375, Pg.118 - End Concrete Monument
- 3.) 1975-Johnson & Anderson; Survey L. Pg. - End
- 4.) 1991-Kennedy, P.S. #17623; Unrecorded Survey - End 1" Iron Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - End Concrete Monument at the Northeast corner of "Oxford Lakes Subdivision No 8" recorded in Liber 221 of Plats, on pages 12-17 of Oakland County Records.

Witnesses from LCRC #1, 2 and unrecorded survey #4 were used to recover and verify the location of the found Concrete Monument

I accepted the found Concrete Monument as the best evidence of the corner position that is being accepted and used.

FIELD MEASUREMENTS BETWEEN

- J-8 to J-9 2772.23 Ft. (H. Kennedy 1991)
- 2772.53 Ft. (H. Kennedy 1992)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-9 I placed a 2" diameter brass cap stamped Oakland County Remonumentation, PS, 17623 on a existing Concrete Monument
- N16°E 39.00' Set PK & Remon. Washer NW face 8" Elm
- N28°E 22.97' Set PK & Remon. Washer NW face 9" Elm
- S25°W 61.38' NE corner of house #677
- S55°W 87.92' NW corner of house #677

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date December 12, 1994

