

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

94 242448

OK - T. SMITH

For corners in  
Oakland  
(County)

Located In: Oxford Corner Code ##  
Township

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
8 SEP 94 3:20 P.M. RECEIPT# 1348  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 1-5-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

1. Public Land Survey	T	5	N	10	E	K-1
	T		R			
	T		R			
	T		R			
2. Property Controlling in Section	S		T		R	
	S		T		R	
3. Miscellaneous Property in Sec.	S		T		R	
	S		T		R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		3		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on November 4, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817 GLO - Wampler, D.S.; Set post; 12" White Oak N47°W 4.32 chains  
1975 Anderson, P.S. #11495; LCRC L.6462, Pg.888-889 - Fnd 1/2" iron rod

*Handwritten signature/initials*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Huston Kennedy, P.S. #17623 - Fnd 1/2" iron rod in the center of the intersection of Davison Lake Road and Barber Road to the South. Both are gravel roads. The witness trees from the LCRC are still existing, but the witness points are grown over. The witness trees were used to recover and verify the fnd 1/2" iron rod.

I accepted the found 1/2" iron rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 I replaced the found 1/2" iron rod with a 5/8" x 24" iron rod with a 2" diameter cap stamped Oakland County Remonumentation P.S. #17623.

- S61°E-39.76 ft-Set PK/Remon. Tag SW face 10" Oak
- N24°E-25.62 ft-Set PK/Remon. Tag West face 13" Cherry
- N12°W-23.76 ft-Set PK/Remon. Tag East face 16" Oak
- S68°W-48.57 ft-Set PK/Remon. Tag North face 24" Oak

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original position.

Signed by [Signature]  
Surveyor's Michigan License No. 17623

Date March 23, 1994

